Maharashtra State Board of
Secondary & Higher Secondary Education,
Pune, S.R.No.832-A, Final Plot No. 178,179,
Near e-Balbharti, Behind Agharkar
Research Institute, Bhamburda,
Shivajinagar, Pune-411004.

महाराष्ट्र राज्य माध्यमिक व
उच्च माध्यमिक शिक्षण मंडळ पुणे
स.न.८३२-ए, फा.प्लॉ.नं.१७८,१७९,
ई-बालभारती शेजारी, आघारकर रिसर्च
इन्स्टिटयूटच्या मागे, भांबुर्डा, शिवाजीनगर,
पुणे ४११००४.

Tel : Chairman (P) : STD . (020)-25651751 Secretary(P) : 25651750 & EPABX -25705000 Fax : 25665807 &
Email : secretary.stateboard@gmail.com

क्र.रा.मं./भांडार-2/2961
पुणे- 411 004
दि.- 13/07/2026

प्रति,

1. मंडळाच्या नोटीसबोर्डवर प्रसिध्द करावयाची प्रत.
2. मंडळाच्या संकेत स्थळावर प्रसिध्द करावयाची प्रत.

विषय:-राज्यमंडळ कार्यालय व परिसरात नव्याने सी.सी.टी.व्ही. यंत्रणा नव्याने कार्यान्वित करणेसाठी दरपत्रक सादर करणेबाबत...

उपरोक्त विषयाचे अनुषंगाने कळविण्यात येते की, राज्यमंडळ कार्यालय व परिसरात नव्याने सी.सी.टी.व्ही. यंत्रणा कार्यान्वित करणेकरिता खालील विवरणाप्रमाणे CP PLUS, GODREJ, PANASONIC, SONY या नामांकित कंपन्यांचे साहित्यासह पुरवठ्यासाठी सविस्तर दरपत्रक सादर करावयाची आहेत.

Sr.No.	Item Description	Quantity	Item No.	Unit	Rate	Amount
1)	Supplying and erecting HMS PVC conduit 25mm dia. with PVC accessories on wall/ceiling as per specification no. WG-A/CON.	1200	1-2-4	M		
2)	Supplying and erecting HMS PVC conduit 32mm dia. with PVC accessories on wall/ceiling as per specification no. WG-A/CON.	300	1-2-4	M		
3)	Supplying and erecting PVC trunking (PVC casing-n-capping) of size 32mm with accessories on wall/ceiling as per specification	300	1-2-8	M		
4)	Supplying and installing LSZH sheathed HDPE insulated copper cat-6 cable suitable for networking compliant with ANSI/TIA	1890	19-3-2	M		
5)	Supplying & erecting mains with 2x2.5 sq.mm FRLSH copper PVC insulated wire laid in provided conduit/trunking/inside pole/bus	90	1-3-2	M		
6)	Supplying & erecting mains with 1x2.5 sq.mm FRLSH copper PVC insulated wire laid in provided conduit/trunking/inside pole/bus	90	1-3-2	M		

7)	Supplying and erecting modular type switch 6A/10A on provided plate and box with wiring connections complete.	10	1-6-1	Each		
8)	Supplying and erecting modular type 3 pin 6A multi socket with safety shutter on provided plate and box with wiring	10	1-6-10	Each		
9)	Supplying and erecting PVC Surface modular switch box with double mounting plate for 6 module complete.	5	1-6-30	Each		
10)	Supplying and fixing 3 m 24 AWG multi stranded, UTP patch cord of enhanced cat 6A type, compliant ANSI/TIA-568.2-D	1	19-3-21	Each		
11)	Supplying, fixing, and configuring 8-ports managed gigabit, layer-2 switch, 10/100/1000 base-T, PoE smart switch plus 2 SFP erected in provided rack compliant with IEEE 802.3 standards complete.	1	19-4-2	Each		
12)	Supplying, fixing, and configuring 16 ports, POE switch compliant with IEEE 802.3 standards with min. 193W POE capacity	3	19-4-2	Each		
13)	Supplying, installing and testing UTP connector (RJ-45) as per specification no. WG-NAS/UTPC.	104	19-5-1	Each		
14)	Supplying and erecting PVC Surface modular switch box with double mounting plate for 2 module complete.	32	1-6-27	Each		
15)	Supplying & erecting of High definition 4 Megapixel IP IR Bullet Camera with following features	8	19-6-4	Each		
16)	Supplying & erecting of High definition 4 Megapixel IP IR Dome Camera with following features	24	19-6-4	Each		
17)	Supplying, erecting & terminating 5 m HDMI cord low voltage grade minimum 4k compliant to be laid in provided conduits	1	19-1-22	Each		
18)	Supplying, installing, testing & commissioning of 64/80 Ch Network Video Recorder (NVR), suitable connect Min. 64 IP	1	19-6-17	Each		
19)	Supplying & erecting 8TB internal Surveillance HDD suitable for SATA Port of NVR, interface transfer rate 6 GB/S, maximum	3	19-6-20	Each		

20)	Supplying and fixing 2U wall mount rack (Dimension-DxWxH-400x550x169 mm) as per specification no. WG-NAS/RAK	4	Non CSR	Each		
21)	Supplying and installing PBT loose tube HDPE sheathed armoured single mode optical fiber cable with 6 fiber, core dia	350	19-3-9	Mtr		
22)	OFC Splicing, Patch Cord, Joint Box, Connectors and etc.	4	Non CSR	Each		
Total						
18% GST						
Total						

उपरोक्त प्रमाणे राज्यमंडळ कार्यालय व परिसरात नव्याने सी.सी.टी.व्ही. यंत्रणा कार्यान्वित करणेकरिता कामाची पहाणी करुन, सदर कामाचे सविस्तर दरपत्रक सर्व करांसह सीलबंद पाकिटात या कार्यालयास दि. 21/07/2026 पर्यंत कार्यालयीन वेळेत प्रत्यक्ष किंवा टपालाने सादर करण्यात यावेत.

सदरची यंत्रणा कार्यान्वित केल्यानंतर सदर यंत्रणेबाबतच्या वार्षिक देखभाल दुरुस्ती (Annual Maintenance Contract) चा कालावधी हा 3 वर्षांसाठी असेल याची नोंद घेण्यात यावी तसेच दरपत्रकासोबत शॉप ॲक्ट प्रमाणपत्र, पॅनकार्ड व आधारकार्ड इत्यादीची प्रत व दरपत्रक सादर करणा-यांचे हमीपत्र सोबत जोडावे, दरपत्रकासह या दस्ताएवजाचे पाकिट सीलबंद करुन त्यावर **"सी.सी.टी.व्ही. यंत्रणा कार्यान्वित करणेकरिता साहित्य पुरवठ्यासाठी दरपत्रक"** असा स्पष्ट उल्लेख करावा. विहित वेळेत आलेल्या व उपरोक्त प्रमाणे अटींची/कागदपत्रांची पूर्तता करतील अश्याच दरपत्रकांचा विचार केला जाईल, तसेच संपूर्ण काम झाल्यावर देयक अदा केले जाईल, याची नोंद घ्यावी.

(मा. अध्यक्ष यांचे मान्यतेने)

Mali

(डॉ.दिपक माळी)
सचिव,
राज्य मंडळ, पुणे-04.