Maharashtra State Board of
Secondary & Higher Secondary Education,
Pune, S.R.No.832-A, Final Plot No. 178,179,
Near e-Balbharti, Behind Agharkar
Research Institute, Bhamburda,
Shivajinagar, Pune-411004.

महाराष्ट्र राज्य माध्यमिक व
उच्च माध्यमिक शिक्षण मंडळ पुणे
स.न.८३२-ए, फा.प्लॉ.नं.१७८,१७९,
ई-बालभारती शेजारी, आघारकर रिसर्च
इन्स्टिटयूटच्या मागे, भांबुर्डा, शिवाजीनगर,
पुणे ४११००४.

Tel : Chairman (P) : STD . (020)-25651751 Secretary(P) : 25651750 & EPABX -25705000 Fax : 25665807 &
Email : secretary.stateboard@gmail.com

क्र.रा.मं./भांडार-2/2960
पुणे-411 004
दि.- 13/07/2026

प्रति,

1. मंडळाच्या नोटीसबोर्डवर प्रसिध्द करावयाची प्रत.
2. मंडळाच्या संकेत स्थळावर प्रसिध्द करावयाची प्रत.

विषय:-राज्य मंडळ प्रशासकीय इमारतीच्या आवारात सोलर स्ट्रीट लाईट यंत्रणा कार्यान्वित करणेसाठी दरपत्रक सादर करणेबाबत...

उपरोक्त विषयाचे अनुषंगाने कळविण्यात येते की, राज्य मंडळ प्रशासकीय इमारतीच्या आवारात सोलर स्ट्रीट लाईट यंत्रणा कार्यान्वित करणेकरिता खालील विवरणाप्रमाणे OSRAM, PHILIPS, CROMPTON, HAVALS, WIPRO व BAJAJ या नामांकित कंपनीचे साहित्यासह पुरवठ्यासाठी सविस्तर दरपत्रक सादर करावयाची आहेत. तसेच

Sr. No.	Item Description	Quantity	Rate Per Item	Amount	GST	Amount
1)	**Solar Street Light (50 W)** Specifications- SSL Semi Integrated Lens Model 50w LiFePO4 Certification-MNRE/NABL/BIS Certified Model-Lens Model Semi Integrated Light-50W, LED 140LM/Watt, IP65 Panel 165Wp, Mono (MBB)MNRE/IEC/NABL Approved Battery Inbuilt 48AH 12.8v LiFePo4 BIS Approved Controller MPPT Dusk To Dawn, Dimming- 50% after 4 hours Protection, Battery Over Charge, Short Circuit, Reverse Flow, Reverse Polarity, Deep Discharge Pole Mounting Accessories - Panel Stand, Luminary Arm Warranty - 5 Years for Complete System	20				

2)	**Pole -** Octagonal Pole 6 Meter Height - 6 Meter (20 Feet) Thickness 3 mm OD Top-70 mm OD Bottom 130 mm Baseplate (L*W*T) - 220*220*12 mm Finishing - Superior Finish Anti-rust coating Corrosion Property- Greater Resistance to corrosion **J Bolt-** Foundation J Bolt 20 750 mm 001 Foundation J Bolt No of Bolts4 Nos in a set Diameter - 20 mm Length - 750 mm	**05**				
3)	Solar High mast Light - Specifications - Certification-MNRE/NABL/BIS Certified Model - Back Choke Flood Light Solar High Mast Light-40W 4, OSRAM LED 140LM/Watt, IP65 Panel-500Wp (125Wp* 4) Mono(MBB) MNRE/IEC/NABL Approved Battery-288AH (SB 72AH 4, 12.8V) LiFePo4 BIS Approved Controller - MPPT Dusk To Dawn, Dimming 50% after 4 hours Protection - Battery Over Charge, Short Circuit, Reverse Flow, Reverse Polarity, Deep Discharge Pole Mounting Accessories - Panel Stand, 4 Sided Luminary Arm, Battery Box Warranty - 5 Years for Complete System (Specification)	**01**				
4)	**LED Street Light 100 (w)** • 25000 Burning Hours • IP65 Waterproof • CRI>80 • >0.9 Power Factor • 100Lm/W Lumens Efficacy • 4.0KV Surge Protection	**10**				
Total						

उपरोक्त प्रमाणे राज्य मंडळ प्रशासकीय इमारतीच्या आवारात सोलर स्ट्रीट लाईट यंत्रणा कार्यान्वित करणेकरिता कामाची प्रत्यक्ष पहाणी करुन, सदर कामाचे सविस्तर दरपत्रक सर्व करांसह सीलबंद पाकिटात या कार्यालयास दि. 21/07/2026 पर्यंत कार्यालयीन वेळेत प्रत्यक्ष किंवा टपालाने सादर करण्यात यावेत.

सदरची यंत्रणा कार्यान्वित केल्यानंतर सदर यंत्रणेबाबतच्या वार्षिक देखभाल दुरुस्ती (Annual Maintenance Contract) चा कालावधी हा 5 वर्षांसाठी असेल याची नोंद घेण्यात यावी तसेच दरपत्रकासोबत शॉप ॲक्ट प्रमाणपत्र, पॅनकार्ड, आधारकार्ड व GST नोंदणी प्रमाणपत्र इत्यादीची प्रत व दरपत्रक सादर करणा-यांचे हमीपत्र सोबत जोडावे, दरपत्रकासह सदर दस्ताऐवजाचे पाकिट सीलबंद करुन त्यावर **"राज्य मंडळ प्रशासकीय इमारतीच्या आवारात सोलर स्ट्रीट लाईट यंत्रणा कार्यान्वित करणेकरिता साहित्य पुरवठ्यासाठी दरपत्रक"** असा स्पष्ट उल्लेख करावा. विहित वेळेत आलेल्या व उपरोक्त प्रमाणे अटींची/कागदपत्रांची पूर्तता करतील अश्याच दरपत्रकांचा विचार केला जाईल, विहित वेळेनंतर आलेल्या दरपत्रकांचा विचार करण्यात येणार नाही. तसेच संपूर्ण काम झाल्यावर देयक अदा केले जाईल, याची नोंद घ्यावी.

(मा. अध्यक्ष यांचे मान्यतेने)

(डॉ.दिपक माळी)
सचिव,
राज्य मंडळ, पुणे-04.